BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2017-18/BD/WORK_INDENT27324

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/09/2017-18, Date: 09.10.2017

Construction of Bangalore One Center Building in Coffeboard Layout ward no. 7 Byatarayanapura

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K SHANKAR REDDY	
				In Figures	In Words
1	107.61	Earth work excavation for foundation of building water sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of colds complete as per specifications.	cum	180.0	Rupees One Hundred Eighty Only
2	18.52	Providing and laying in position plain cement concrete of nominal mix 1:4:8 using 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms . Thick, well compacted in foundation and plinth, includign cost of all materials, labour, HOM of machinery curing complete as per specifications	cum	5200.0	Rupees Five Thousand Two Hundred Only
3	15.12	Providing and constructing granite /trap/ baslat size stone masonry in foundation with cement mortar 1:6, stones hammerd dressed in courses not less than 20cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications (Page No. 23, Item No. 5.6)	cum	4500.0	Rupees Four Thousand Five Hundred Only
4	7.61	Providing and onstructing granite /trap/ baslat size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications	cum	5300.0	Rupees Five Thousand Three Hundred Only
5	14.4	Providing ruled pointing to coursed stone masonry with cement mortar 1:3 20mm deep, after raking joints to depth of 20mm necely lining, including cost of materials, labour, curing complete as per specifications	sqm	60.0	Rupees Sixty Only
6	107.61	Filling avaialble excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms in depth compacting each deposited layers by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specification	cum	120.0	Rupees One Hundred Twenty Only
7	33.64	Providing and laying in position reinforced cement concrete of nominal mix 1:1.5:3 with 20mm (M20) and down size graded granite machine mixed , concrte laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, stair case, lintels retaining walls,return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, bustress, string or lacing courses, parapets, coping bed blocks, anchors blocks, plain windows cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing complete as per specifications	cum	5000.0	Rupees Five Thousand Only
8	6.12	Providing and laying in position reinforced cement concrete 1:1.5:3 (M20) with 12mm and down size graded metal, machine mixed, well compacted for plain chejja of 7.5cms. Average thickness, upto ground floor level, including cost of all materials, labour, HOM of machinery specification	cum	350.0	Rupees Three Hundred Fifty Only
9	3.36	Providing and fabricating TMT . Steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking,placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design(laps and wasteage shall not measured and paid) cost of materials. labour. HOM of machinery complete as per specifications	tonne	64000.0	Rupees Sixty Four Thousand Only
10	83.2	Providing and removing centering shuttering strutting propping etc., and removal of form work for columns, pillars, abutments, post and struts square/ rectangular/ polygon in plan including cost of all materials labour complete as per specification	Sqm	360.0	Rupees Three Hundred Sixty Only

K. Sankar Reddy

Singature of the contractor

29/01

Executive Engineer

29/01

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K SHANKAR REDDY	
				In Figures	In Words
11	170.41	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs,landing, balconies and likes thickness upto 200mm including cost of materials, labour complete as per specification	sqm	550.0	Rupees Five Hundred Fifty Only
12	144.31	Providing and constructing pre cast concrete solid blocks with compressive strength not less than 35 kg/sqm with cement mortar 1:4 masonry (quoins, jamb,closer blocks) with solid concrete blocks of size 40x20x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials,labour charges,scaffolding,curing etc., complete as per superstructur	sqm	900.0	Rupees Nine Hundred Only
13	0.14	Providing Honne wood frames of doors windows, clerestory windows, ventilators and other frames wrought, framed of assembled including making plaster grooves (excluding cost of materials, labour, HOM of machineries complete as per specifications	sqm	86000.0	Rupees Eighty Six Thousand Only
14	2.52	Providing and fixing in position fully panelled Honne wood shutters for doors, styles and rails of 40mm, thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour,HOM of machineries completed as per specification (excluding cost of fixtures)	sqm	5000.0	Rupees Five Thousand Only
15	1.58	Providing and fixing in position shutters for doors made out of Honne wood styles and rails of 35mm. Thick with bottom and lock rail 180mm wide top rail and styles 100mm wide as per drawings and panels of 18mm thick is exteriors grade melamine impregnated prelaminations particle board colour on one sides including cost of materials, labour, HOM of machineries complete as per specifications.(excluding cost of fixtures)	nos	3500.0	Rupees Three Thousand Five Hundred Only
16	162.54	Providing and fixing M.S. grill work for windows and ventilator weighing 21kg/Sqm using M.S. flats, or M.S square rods or combination of M.S. flats and steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures labour and HOM of machinery specifications	kg	75.0	Rupees Seventy Five Only
17	7.74	ventilators as per approved drawings with sliding shutters using double track window frame section of size 122.2x31.75mm with 1.2mm thick, bottom section weight of 0.695 kg per m, sides and top section of 1.3mm thick weight of 0.659 kg per m and shutter comprising top and bottom section of size 40mmx18mm , 1.25mm thick of 0.417 kg per m shutter outer side 40mmx18mm, 1.25mm thick weight of 0.417 kg per m, shutter interlock section 40mmx 26.7mm , 1.1mm thick, wieght of 0.469 kg per m the shutter mounted on nylon roller with approved quality of fixture such as alluminium tower bolts etc., and providing and fixing 5.5mm thick plain glass of shutter fitted with rubber beading alluminium section anodized 12 to 15 microns including cutting to required length, joints mitred sub dividing the frame tenonned revited in the assembled frame stiffened with end clips at corners angles etc., and fixed to walls, lintles, floor beams or cills as the case may be with necessary steel screws, raul plugs, or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar, alluminium section pre treated for removal of any rust and	nos	3800.0	Rupees Three Thousand Eight Hundred Only
18	105.5	Providing 18mm thick cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering: providing and removing scaffolding, including cost of materials labour curing complete as per specifications	sqm	240.0	Rupees Two Hundred Forty Only
19	83.76	Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling incluidng rounding off corners wherever required smooth rendering providing and removing scaffolding including cost of materials, labour curing complete as per specification	sqm	170.0	Rupees One Hundred Seventy Only
20	189.26	Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing complete as per specifications	sqm	20.0	Rupees Twenty Only
21	222.64	Providing 20mm thick cement plaster in single coat with cement mortar 1:3, to stone masonry & concrete surface including rounding off corners wherever required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications	sqm	250.0	Rupees Two Hundred Fifty Only

K. Sankar Reddy

Singature of the contractor

29/01

Executive Engineer

29/01

Sl. No	Approved Qty.	Description	Unit	Approved Tender Rates of K SHANKAR REDDY	
				In Figures	In Words
22	55.64	Providing vitirfied tiles 60x60cms of approved make shade and size for flooring laid on a bed of 12mm thick cement mortar 1:3 mix flush pointing with white cement using colour pigment, including cost of materials, labour, complete as per specifications	sqm	1000.0	Rupees One Thousand Only
23	62.04	Providing and laying integral cement based water proofing treatment including preparation of surface as required for treatment of roofs, balconies terraces etc., consisting of following applications a) applying and grouting a slurry coat of neat cement using 2.75 kg per sqm of cement admixed with proprietary water proofing compound confirming to IS 2645 over the RCC slab after cleaning the surface before treatment b)laying cement concrete using broken brick bats 25mm to 100mmsize with 50% of cement mortar 1:5 admix with propreatory water proofing compound confirming IS 2645 over 20mm thick layer of cement mortar 1:5 admix with proprietary water proofing compound to required slope and treating similarly the adjoining walls upto 300mm height including rounding off junctions of walls and slabs c)after two days of proper curing applying a second coat of cement slurry admix with preprietoray water proofing compound d) finishing the surface with 20mm joint less cement mortar of mix 1:4 admix with preprietary water proofing compond wall finally finishing the surface with travel and neat cement slurry and making of 300 x 300 mm square e)	sqm	950.0	Rupees Nine Hundred Fifty Only
24	6	Providing and fixing on wall surface 4.0kg?Sq.cm H.D.P.E. rain down water pipes 90mm outer dia approved make and brand with necessary specials like shoes, bends and offsets fixed with iron clamps, wall plugs, screws, including cost of materials, labour, complete as per specification	mtr	450.0	Rupees Four Hundred Fifty Only
25	1	Providing and fixing white vitreous china clay water closet European type (pedestal type , P-trap) with black solid plasit seat and lid C.P. brass hinges rubber buffers 10 litre low level P.V.C. flushing cistern (all are approved make) with fittings, C.I / M.S. brackets. 40mm diameter flush bend with fittings and clamps, overflow arrangements design, painting of fittings and brackets, cuttings and making good the wall and floor wherever required including cost of materials labour complete as per specifications	nos	5500.0	Rupees Five Thousand Five Hundred Only
26	1	Providing and fixing white vitreous china clay flat back wash basin size 630x450mm with a single of 15mm C.P. brass pillar taps with C.I. /M.S. brackets 32mm C.P. brass waste of standard pattern, painting of fittings and brackets, cuttings and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications	nos	2200.0	Rupees Two Thousand Two Hundred Only
27	3.4	Providing ceramic tiles of approved make shade and size for flooring, treads of steps and landing laid on a bed of 12mm thick , cement mortar 1:3 mix, flush pointing using white cement using colour pigment including cost of a materials, labour, curing, complete as per specifications Ceramic Tiles 30x30cms 6mm th.	Sqm	1250.0	Rupees One Thousand Two Hundred Fifty Only
28	15.54	Providing skirting, dado rises of steps with colour glazed tiles 30x45cms 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (Exclude cost of rough plastered surface which should be measured and paid separetely) using glazed tiles of approved make and size including cost of materials labour complete as per specifications	sqm	1100.0	Rupees One Thousand One Hundred Only
29	2	Providing and fixing 7.5cms to 15cms dia NP grating 100mm dia	nos	150.0	Rupees One Hundred Fifty Only
30	4	Providing and fixing C.I. Nahani trao of approved make conforming to ISI specificatins and constructin of Cistern in CC 1:2:4 as per directions (Rate is inclusive of cost of materials and fixture and conveyance of materials to work spot) 10cms to 7.5cms	nos	220.0	Rupees Two Hundred Twenty Only
31	50	Providing and fixing chorinated poly venyl chloride (CPVC) pipes conforming to IS15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. this includes jointing of pipes and fittings with one step CPVC solvent cement and the cost of cutting chases & making good the same including testing of joints complete 20mm nominal OD Pipes	mtr	180.0	Rupees One Hundred Eighty Only

K. Sankar Reddy
Singature of the contractor

29/01
Executive Engineer
29/01

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K SHANKAR REDDY	
				In Figures	In Words
32	2	Providing and fixing in position brass stop cock of approved quality15mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications	nos	170.0	Rupees One Hundred Seventy Only
33	3	providing and fixing in position brass gate valve with C.I. Wheel of approved quality (Screwed end) 20mm nominal bore including cost of all materials labour and HOM of Equipments with all lead complete as per specificatins	nos	430.0	Rupees Four Hundred Thirty Only
34	30	Providing and fixing to wall, ceiling and floor unplasticised PVC 6.00 kgs/sqcm working pressure with pipe fittings, wall clips etc., and making good the wal, ceiling and floor for sanitary pipe line including cost of all materials charges HOM of acquirements and testing complete as per specification 160mm dia	mtr	800.0	Rupees Eight Hundred Only
35	4	Providing NP/CP waste union conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spot etc., complete 32mm dia	nos	130.0	Rupees One Hundred Thirty Only
36	2	Construction brick masonry inspection chamber 450x450mm and 450mm depth (clear inside dimension) for single pipes line using table mouled non-modular bricks of class designation 50 in cement mortar 1:5 C.I. cover witth frame (light duty) 450x450mm	nos	5700.0	Rupees Five Thousand Seven Hundred Only
37	1	Providing and placing on terrace , polyethylene water storage tanks with manhole lid and suitable locking arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications (For 1000 litre capacity)	nos	9000.0	Rupees Nine Thousand Only
38	83.76	Providing applying two coats of wall putty to inside plasterd walls and ceiling using white cement putty. Scrapping and levelling the surface using steel blade and preparing the surface even and smooth by using different grade sand papers, including cost of all materials, cost of labour and scaffolding etc., complete as per the specifications	sqm	50.0	Rupees Fifty Only
39	189.26	Providing and applying painting two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after throughly brushing the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specificationswith primer	sqm	80.0	Rupees Eighty Only
40	222.64	Providing and finishing external walls in two coats over one coat of 100% acrylic silicon glazed primer with antifungal paint for top coat of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered materials, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications	sqm	150.0	Rupees One Hundred Fifty Only
41	16.95	Applying priming coat over new wood surface and/ or wood based surface after preparing the surface after throughly cleaning oil, grease, dirt and foreign matter, sand papering and knotting liquid wood filler, for varnish including cost of materials, labour, complete as per specificatios	sqm	38.0	Rupees Thirty Eight Only
42	16.95	Providing and applying painting two coats (excluding priming coat) on new wood surface and/ or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications	sqm	80.0	Rupees Eighty Only
43	1	Supply of MONOBLOCK TYPE_MB SERIES THREE PHASE) motor 1 HP of make ATALANTA/SUGUNA/CRI/KIRLOSKAR PUMPS	nos	8000.0	Rupees Eight Thousand Only

K. Sankar Reddy
Signature of the Contractor

29/01
Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

29/01